

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BENZIE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 27N R 14W K-6
 T _____ R _____
 T _____ R _____
 T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____

2. Property Controlling
 in Section

3. Miscellaneous
 Property in Sec.

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

I, CARL KIISKILA, in a field survey on JULY 3, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14	●	13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 K-6

6.L.O. SET POST - 14" SUGAR MAPLE N04°W 18.5', 10" HEMLOCK S18°E 2.0'. NO EVIDENCE OF THIS 6.L.O. POST OR BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6

REESTABLISHED CORNER BY SINGLE PROPORTIONATE MEASUREMENT MIDWAY AND ON LINE BETWEEN A FOUND CORNER TO THE NORTH AND A REESTABLISHED CORNER TO THE SOUTH. N-S WINDING TRAIL IS 120'+/- WEST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6

SET 4"x 36" CONC. MON. WITH BENZIE CO REMON PROGRAM
 BRASS CAP AND SET CARSONITE POST.

5" BEECH N30°W 5.64'
 11"TW.S.MAPLE N40°E 23.87'
 9"TW.S.MAPLE S45°E 15.35'
 12"TW.S.MAPLE S20°W 15.09'



Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-8-97