

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>BENZIE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>14W</u>	<u>J-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, CARL KIISKILA, in a field survey on DECEMBER 19, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
J-7

G.L.O. SET POST - 16" SUGAR MAPLE S64°E 11.2', 12" BEECH N48°W 28.4'. NO EVIDENCE OF THIS G.L.O. POST OR BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-7

REESTABLISHED S1/4 CORNER OF S-14 BY SINGLE PROPORTIONATE MEASUREMENT MIDWAY AND ON LINE BETWEEN REESTABLISHED CORNERS TO THE EAST AND WEST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-7

SET BENZIE CO. REMON. MON AND CARSONITE POST.

18" TW. MAPLE	N40°W	31.02'
8" R. PINE	S50°E	80.71'
11" B. CHERRY	S10°E	40.64'
5" MAPLE	S65°W	49.44'



Signed by Carl T Kiiskila
Surveyor's Michigan License No. 33981

Date 4-8-97