

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BENZIE</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>27N</u> R <u>14W</u>	<u>1-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, CARL KIISKILA, in a field survey on MAY 30, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15	●	14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 I-6

G.L.O. SET BEECH POST - 15" SUGAR MAPLE S78°W 20.5', 8" BEECH N87°E 8.6'. NO EVIDENCE OF THIS G.L.O. POST OR BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 I-6

SET CORNER BY SINGLE PROPORTIONATE MEASUREMENT BETWEEN FOUND SECTION CORNER TO THE NORTH AND REESTABLISHED CORNER TO THE SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 I-6

SET BENZIE CO. REMON MON. W/BRASS CAP AND CARSONITE POST  
 12" TRI. MAPLE N70°W 25.38'  
 4" IRONWOOD N10°W 10.01'  
 7" W.PINE S30°E 27.42'  
 8" W.PINE S20°W 31.09'



Signed by Carl T. Kiiskila  
 Surveyor's Michigan License No. 33981

Date 4-8-97