

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|------------------------------------|---------------------------|---------------|
| <u>BENZIE</u> | Located In: | Corner Code # |
| (County) | | |
| 1. Public Land Survey | T <u>27N</u> R <u>14W</u> | <u>1-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property In Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL KIISKILA, in a field survey on MAY 29, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 10 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:
 I-7

G.L.O. SET MAPLE POST - 12" SUGAR MAPLE N37°E 9.2', 10" BIRCH S22°W 27.1'. NO EVIDENCE OF THIS G.L.O. POST OR BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 I-7

SET 4"X 36" CONC. MON. W/3" BRASS BENZIE CO. RE-MON PROGRAM CAP, PER MAX HARRIS JUNE 19, 1991 (FILE No. 91-6-1465) CERT. OF SURVEY DATA. N. HARRIS CALCULATED A POSITION FOR THIS CORNER DOUBLE PROPORTION, 1-MILE TO E-W-S-N (THE POSITION 1-MI TO EAST WAS ALSO A CALCULATED POSITION, SINGLE PROPORTION 1-MI N & 2-MI SOUTH). CTR OF OLD NARROW N-S GRADE IS 11'+/- EAST (MOSTLY OVER GROWN).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 I-7

SET BENZIE CO. RE-MON CONC MON. & CARSONITE POST.
 6" MAPLE N40°W 18.95'
 5" W. PINE N50°E 15.09'
 10" W. PINE S55°E 25.75'
 11" W. PINE S32°W 15.81'

6" SPIKE W/RENOW WASHER USED ON WIT. TREES.



Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-8-97