

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>BENZIE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>14W</u>	<u>6-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling In Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL KIISKILA, in a field survey on AUGUST 13, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7							●						
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 6-7

G.L.O. SET POST - 18" BEECH N73°W 15.2', 16" BEECH S26°E 11.2'. NO EVIDENCE OF THIS G.L.O. POST OR BEARING TREES WAS FOUND. LAND SURVEYOR R. MAX HARRIS, PS025845, FOUND AND ACCEPTED AN AXLE SHAFT AS THE CORNER COMMON TO SECTIONS 15, 16, 21 & 22 AND LEFT IT IN PLACE. MICH. DNR PERSONNEL FOUND AND ACCEPTED CORNER AS ACCEPTED BY R. MAX HARRIS, 1991 L.C.R.C. LIBER 1, PAGE 272.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6-7

FOUND AXLE SHAFT PER R. MAX HARRIS L.C.R.C. AND WITNESSES. CORNER FITS G.L.O. DISTANCES N, S & E WELL.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

6-7

SET 4" x 36" CONC MON W/BRASS BENZIE CO REMON PROGRAM CAP AND MON BOX IN PLACE OF FOUND 1" x 20" AXLE SHAFT.
 18" LOCUST N25°E 87.17'
 9" R.PINE S55°E 87.99'
 3" S.MAPLE S35°E 80.07'
 120" ASPEN S22°W 75.60'
 CORNER IS IN CTR. OF N-S B.TOP ROAD.
 1 = PS M.HARRIS 1991 MIT.



Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-8-97