

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BENZIE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 27N R 14W 6-9

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, CARL KIISKILA, in a field survey on JULY 10, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
6-9

6.L.D. SET POST - 10" SUGAR MAPLE NO BEARING 16.5', 18" HEMLOCK N9°E 22.4', NO EVIDENCE OF THIS 6.L.D. POST OF BEARING TREES WAS FOUND. R.MAX HARRIS, PS #25845, 1991 L.C.R.C. FOUND 5/8" IRON BAR.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6-9

FOUND 3/4" REROD FITTING R. MAX HARRIS L.C.R.C. AND WITNESSES OF 1991.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

6-9

FD 3/4" REROD, REPLACED W/4"x 36" CONC MON W/BENZIE CO RENOM PROGRAM BRASS
CAP AND SET CARSONITE POST.

13" BASSWOOD	N68°W	6.05'
113" MAPLE	N40°E	19.29'
114" MAPLE	S64°E	13.62'
15" MAPLE	S12°W	9.29'

1 = PS M.HARRIS WIT.

Signed by Carl T. Kiiskila
Surveyor's Michigan License No. 33981

Date 4-8-97

