

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BENZIE</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>27N</u> R <u>14W</u>	<u>H-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property In Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, CARL KIISKILA, in a field survey on JULY 9, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 H-9

G.L.D. "SET POST - BEECH 10 N38°W †, HEMLOCK 8 S41°E †, † THE DISTANCE TO THE BEARING AT THIS QR. SEC. CORNER WERE, THROUGH CARELESSNESS, OMITTED IN PUTTING DOWN THE NOTES". - NO EVIDENCE OF THIS POST OR BEARING TREES WAS FOUND. R.MAX HARRIS, PS 825845, SET 1/2" RRD BY PROPORTIONATE MEASUREMENT JUNE 1991 L.C.R.C. LIBER 1, PAGE 272.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-9  
 FOUND 1/2" REROD FITTING R. MAX HARRIS WITNESSES AND JUNE 1991 L.C.R.C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 H-9

REPLACED FD 1/2" REROD W/4" x 3/8" CONC. NON M/BENZIE CO REMON PROGRAM BRASS CAP AND SET CARSONITE POST.  
 4" S. MAPLE N85°W 34.15'  
 2 1/2" BASSWOOD N40°W 33.63'  
 10" S. MAPLE N15°W 34.96'  
 10" IRONWOOD N20°E 35.33'  
 3" B. CHERRY S35°E 13.09'

† = PS, M.HARRIS 1991 MIT.



Signed by Carl T. Kiiskila  
 Surveyor's Michigan License No. 33981

Date 4-8-97