

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 27 N.R. 15W


BENZIE COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 28-29-32-33

CORNER MONUMENT Set Std. Dept. Mon.

DATE MONUMENT PLACED AND WITNESSED June 1968

WITNESSES TO CORNER..... 3" W. Pine N 18 E 18.1'



3" Cedar S 13 E 4.3'

3" Cedar S 65 W 18.1'

AND N-S Random Due W. 14.6'

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set on a projection of the W line of Section 33, from the SW corner of Section 33 through the W 1/4 corner of Section 33; on a pro-rated distance from the W 1/4 corner of Section 33 to the SW corner of section 21 by Shadko survey.

SURVEYOR'S SEAL

SIGNED *Paul F. Roer* DATE 7/9/68  
REGISTERED LAND SURVEYOR 12028