

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 27 N.R. 15 W


BENZIE COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 31 - 32

CORNER MONUMENT Set Std. Dept. Mon.

DATE MONUMENT PLACED AND WITNESSED June 1968

WITNESSES TO CORNER..... 12" W. Pine S 10 W 67.7'



10" W. Pine N 61 W 55.3'

12" R. Pine N 08 W 61.4'

AND N-S Random Due E. 0.7'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner fits location where Ron Haswell says there once was a corner. Also fits data in MSHD survey notes dated 1921, Proj. 010-9. It fits the average line of the old fence remains from M-22 south to the Meander corner near the north shore of Long Lake. Point falls in approximate center of Haswell Road (dirt).

SURVEYOR'S SEAL

SIGNED

Carl F. Boer
REGISTERED LAND SURVEYOR 12028

DATE

7/9/68