

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 27 N.R. 15 W


BENZIE COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 30 - 31

CORNER MONUMENT Set Std. Dept. Mon.

DATE MONUMENT PLACED AND WITNESSED June 1968

WITNESSES TO CORNER..... 7" R. Pine S 50 E 38.4'



10" Oak S 75 W 44.0'

6" Maple N 22 E 22.5'

AND
E-W Random Due N 6.5'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was controlled for direction by a straight line from the SE corner, Section 30 through a GLO Line Tree (now a blazed w. pine stub) at 583 feet west of the line tree. Fits GLO data and F. Haswell data.

SURVEYOR'S SEAL

SIGNED

Paul F. Roer

REGISTERED LAND SURVEYOR 12028

DATE

7/9/68