

✓
MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 27 N.R. 15 W


BENZIE COUNTY

DESCRIPTION OF CORNER Sec. corner common to Sections 19-20-29-30

CORNER MONUMENT Set Std. Dept. Mon.

DATE MONUMENT PLACED AND WITNESSED June 1968

WITNESSES TO CORNER..... 10" W. Pine N 46 W 10.2'



12" Cedar N 27 E 30.3'

8" Cedar S 18 E 16.4'

Random S. Due E. 15.6'

AND E-W Random Due N. 34.1'

Random N. Due E. 11.3'

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set at a record distance (Haswell) North of the SW corner, and at a prorated Gov't distance west of the NE corner as compared to the distance between the SE corner and the SW corner.

SURVEYOR'S SEAL

SIGNED

Carl F. Bauer

DATE

7/9/68

REGISTERED LAND SURVEYOR

12028