


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

BEHZIE COUNTY
T 27 N R 15 W

DESCRIPTION OF CORNER Meander Corner on N 1/8 line Sec. 12, or SW cor of
CORNER MONUMENT Govt. Lot 1.
Set 1" x 36" pipe
DATE MONUMENT PLACED AND WITNESSED 12-7-70

WITNESSES TO CORNER..... 1/2" Pipe by Fraser Due W 214.2'



8" J. Pine S 75 E 27.6'

8" Balsam S 40 E 47.6'

AND

1088.61' West of Ctr. of NW 1/4 Sec. 12.

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a boundary survey in this area. The position for the corner was based on a section subdivision of Sec. 12 by Walt Fraser, NLS, Traverse City. The corner was placed at the intersection of the line between Govt. Lots 1 & 2 with the U.S. Meander line along Lake Michigan shoreline.

SURVEYOR'S SEAL

SIGNED

Carl F. Rosen

DATE

12-14-70

DISTRIBUTION:

REGISTERED LAND SURVEYOR 12028

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68