

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY..... T. <u>27</u> N. R. <u>15</u> W.		K-9; L-9; M-9; M-10
2. PROPERTY CONTROLLING IN SECTION..... T. N. S. R. E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION..... T. N. S. R. E. W.		
4. LOT NO., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 26, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

XX

C. Continued	M-9	M-10
Fd. 1/2" x 12" rerod over 1 1/4" pipe		Fd. 1 1/4" pipe (buried 0.4)
* P. Pole S30°E 37.55		*18" Hemlock S83°E 8.82
* 9" Cherry N10°W 48.73		* 9" Hemlock S45°W 36.64
*20" Maple N56°W 61.86		*14" Ash N30°E 28.02
Set ced. post w/loc tag N 24'		Set ced. post w/loc tag W. 33'
Ctr. E-W gravel Rd. S 9'±		Round conc. mon. W. 33.10
* = Old Wits		Ctr. N-S gravel rd. W. 8'±
		* = Old Wits

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 K-9 Fd. & accepted Benzie Co. mon. for NW cor. Sec. 25. Cor. also used by H. Bruning, RLS #10681 in 1975 survey. Benzie Co. mon. was established by RLS's P. Perla & H. Bruning in 1969 from G.L.O. distance from swale to N. & prop. dist. from cor.'s to E & W.
 L-9 Established N 1/4 cor. Sec. 25 midway & on line btw. fd. sec. cors. 1/2 mile W. & 1/2 mile E. (*pipe set in 1964 Dept. Survey as temp. point only to hold E-W random line pos.)
 M-9 Fd. & accepted rerod over 1 1/4" pipe for NE cor. of Sec. 25. Cor. also fd. in previous Dept. Survey of 1964 & used by H. Bruning, RLS, survey of 1975.
 M-10 Fd. & accepted 1 1/4" pipe for E1/4,S-25 as found in previous Dept. Survey of 1964 & used by RLS, H. Bruning, in 1975.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9	L-9
Fd. 1" I.P. w/Benzie Co. cap.; added ced. post w/loc tag.	Set D.N.R. mon. & ced. post.
*20" Oak N45°E 14.06	3" Oak N57°E 14.9
*13" Oak (twin) N31°W 64.96	8" R. Pine S22°E 7.0
* 8" Oak S52°W 41.43	13" R. Pine N63°W 8.4
Fd 1/2" pipe N01°02'E 112.03	*Fd. 3/4" pipe N00°48'E 56.02
(F.C.W. Trw. Point)	
N-S Tr. Rd. East 24'±	
* Old Wits	


SIGNED BY Carl F. Roser 3-18-81 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ LAKE TOWNSHIP (East Part)
 BENZIE COUNTY