

APR 14 1998

LIBER 2 PAGE 75

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

For corners in

BENZIE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 27N R 14W 6-6
T ___ R ___
T ___ R ___
T ___ R ___

2. Property Controlling in Section

S ___ T ___ R ___
S ___ T ___ R ___

3. Miscellaneous Property in Sec.

S ___ T ___ R ___
S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

15 Jan 1998 4:09:11 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES one

Register of Deeds Stamp & File Number

I, CARL KIISKILA, in a field survey on AUGUST 14, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

6-6

G.L.O. SET POST - 20" SUGAR MAPLE N72°E 13.2', 30" SUGAR MAPLE S20°N 15.2'. NO EVIDENCE OF THIS G.L.O. POST OR BEARING TREES WAS FOUND. F.HASWELL, APRIL 30TH 1896 "PLANTED NEW CEDAR POST AND FILLED HOLE WITH BLACK SAND FROM ORIGINAL WITNESS TREES". R.MAX HARRIS, PS #25845, JUNE 19, 1991 FILE 91-6-1465 CERTIFICATE SHOWS 1/2" IRON ROD FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6-6

FOUND 1/2" REROD FITTING R. MAX HARRIS, P.S. #25845, DISTANCES TO NW COR. AND SW COR. OF SECTION 15.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 12/7/1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

6-6

SET 4"x 36" CONC MON W/3" BRASS BENZIE CO REMON PROGRAM CAP AND MON BOX IN PLACE OF FD 1/2"x 23" REROD AND 1"x 15" GALV. PIPE. MON BOX IS IN APPROX CTR OF 21' WIDE N-S B.TOP RD. CTR OF GRAVEL RD TO WEST IS 5'+/- SOUTH.

- 14" R.PINE S55°W 75.64'
- 2" W.ASH N60°E 43.91'
- 6" R.PINE S55°E 54.52'
- 4"x 4" WOLMANIZED POST BY TELEPHONE RISER S45°W 57.56'



Signed by Carl T. Kiiskila
Surveyor's Michigan License No. 33981

Date 4-8-97