

APR 14 1998

LIBER 2 PAGE 76

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

15 Jan 1998 4:09:26 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES one

For corners in

BENZIE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 27N R 14W 6-7

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, CARL KIISKILA, in a field survey on AUGUST 13, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1								3	2			1
2	6		5		4							
3												
4	7		8		9		10		11			12
5												
6	18		17		16		15		14			13
7												
8	19		20		21		22		23			24
9												
10	30		29		28		27		26			25
11												
12	31		32		33		34		35			36
13												

A. Description of original monument and accessories and/or subsequent restoration:

6-7
G.L.O. SET POST - 18" BEECH N73°W 15.2', 16" BEECH S26°E 11.2'. NO EVIDENCE OF THIS G.L.O. POST OR BEARING TREES WAS FOUND. LAND SURVEYOR R. MAX HARRIS, PS#25845, FOUND AND ACCEPTED AN AXLE SHAFT AS THE CORNER COMMON TO SECTIONS 15, 16, 21 & 22 AND LEFT IT IN PLACE. MICH. DNR PERSONNEL FOUND AND ACCEPTED CORNER AS ACCEPTED BY R. MAX HARRIS, 1991 L.C.R.C. LIBER 1, PAGE 272.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6-7
FOUND AXLE SHAFT PER R. MAX HARRIS L.C.R.C. AND WITNESSES. CORNER FITS G.L.O. DISTANCES N, S & E WELL.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 12/7/1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

6-7
SET 4"x 36" CONC MON W/BASS BENZIE CO REMON PROGRAM CAP AND MON BOX IN PLACE OF FOUND 1"x 20" AXLE SHAFT.
18" LOCUST N25°E 87.17'
9" R.PINE S55°E 87.99'
3" S.MAPLE S35°E 80.07'
120" ASPEN S22°W 75.60'
CORNER IS IN CTR. OF N-S B.TOP ROAD.
= PS M.HARRIS 1991 WIT.



Signed by Carl T. Kiiskila
Surveyor's Michigan License No. 33981

Date 4-8-97