

APR 14 1998

LIBER 2 PAGE 77

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

15 Jan 1998 4:09:39 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES one

For corners in

BENZIE

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 27NR 14W 6-8
 T R _____
 T R _____
 T R _____
- 2. Property Controlling S T R _____
 in Section S T R _____
- 3. Miscellaneous S T R _____
 Property in Sec. S T R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, CARL KIISKILA, in a field survey on AUGUST 13, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21	●	22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

6-8

G.L.O. SET POST - 20" SUGAR MAPLE N75°W 11.9', 18" BEECH S67°E 34.2'. NO EVIDENCE OF THIS G.L.O. POST OR BEARING TREES WAS FOUND. R. MAX HARRIS, PS#25845, 1991 L.C.R.C. LIBER 1, PAGE 272; SET 1/2" IRON ROD PROPORTIONATE TO G.L.O. ON LINE BETWEEN 6-7 & 6-9. JAN. 1993 MICH. DNR FOUND AND ACCEPTED 1/2" IRON WITH CAP FITTING R. MAX HARRIS L.C.R.C.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6-8

FOUND 1/2" IRON ROD PER R. MAX HARRIS L.C.R.C. AND WITNESSES. CORNER FITS G.L.O. DISTANCES N & S WELL.

Attested by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 12/7/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

6-8

SET 4"x 36" CONC MON W/BENZIE CO REMON PROGRAM BRASS CAP AND MON BOX IN PLACE OF FD 1/2" REROD.
 †10" R.PINE WEST 44.02'
 †13" R.PINE N50°W 46.32'
 †12" S.MAPLE S76°E 39.69'
 15" S.MAPLE S50°E 59.94'
 FD 1/2" REROD W/PS CAP BESIDE
 WOLMANIZED POST EAST 32.80'



† = PS, M.HARRIS 1991 WIT.
Signed by Carl T. Kiiskila
Surveyor's Michigan License No. 33981

Date 4-8-97