

APR 14 1998

LIBER 2 PAGE 78

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

15 Jan 1998 4:09:54 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES One

For corners in

BENZIE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 27N R 14W 6-9

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, CARL KIISKILA, in a field survey on JULY 10, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

6-9
G.L.O. SET POST - 10" SUGAR MAPLE NO BEARING 16.5', 18" HEMLOCK N9°E 22.4', NO EVIDENCE OF THIS G.L.O. POST OF BEARING TREES WAS FOUND. R. MAX HARRIS, PS #25845, 1991 L.C.R.C. FOUND 5/8" IRON BAR.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6-9
FOUND 3/4" REROD FITTING R. MAX HARRIS L.C.R.C. AND WITNESSES OF 1991.

Ratified by Peer Group
in accordance with P.A. 345
Chairman [Signature]
Date 12/7/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

6-9
FD 3/4" REROD, REPLACED W/4"x 36" CONC MON W/BENZIE CO REMON PROGRAM BRASS CAP AND SET CARSONITE POST.
13" BASSWOOD N68°W 6.05'
#13" MAPLE N40°E 19.29'
#14" MAPLE S64°E 13.62'
#5" MAPLE S12°W 9.29'

† = PS M.HARRIS WIT.

Signed by Carl T. Kiiskila
Surveyor's Michigan License No. 33981

Date 4-8-97

