

APR 14 1998

LIBER 2 PAGE 81

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

For corners in

BENZIE

(County)

Located in:

Corner Code #

1. Public Land Survey

T 27N R 14W H-7

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

15 Jan 1998 4:10:37 PM

NICHELLE R. GRAY

REGISTER OF DEEDS

PAGES One

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, CARL KIISKILA, in a field survey on OCTOBER 3, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7								●					
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
H-7

G.L.O. SET POST - 12" BEECH S20°E 17.2', 8" SUGAR MAPLE N14°W 21.1', 1850 RESURVEY OF SUBDIVISION OF TOWNSHIP. NO EVIDENCE OF THIS G.L.O. POST OR WITNESS TREES WAS FOUND. FOUND 1/2" PIPE 12.3' EAST OF CALCULATED SINGLE PROPORTIONATE POSITION PER R. MAX HARRIS, PS #25845, CERTIFICATE FITTING HIS WITNESSES. AFTER A DISCUSSION WITH M.HARRIS IT WAS DETERMINED THAT A TEMPORARY POINT WAS APPARENTLY WITNESSED IN ERROR.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7

SET 5/4 CORNER SEC. 15 MIDWAY AND ON LINE BETWEEN FOUND SECTION CORNER TO THE WEST AND REESTABLISHED SECTION CORNER TO THE EAST. CORNER FITS M.HARRIS CERT. OF SURVEY DATED JUNE 19, 1991; FILE NO. 91-6-1465. CTR OF OLD RR GRADE, NOW TRAIL ROAD, NE-SW IS 66' WEST. FD OLD 1 1/2" x 12" SOLID IRON, BENT, N70°W 28.9'.

Ratified by Peer Group
In accordance with P.A. 345

Chairman [Signature]

Date 12/7/1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7

SET D.N.R. MON. & CEDAR POST.
26" B.CHERRY N25°E 37.05'
16" B.CHERRY N85°E 57.04'
14" MAPLE S50°E 48.19'
13" TW.B.CHERRY S25°E 38.71'
FD 1/2" REROD W/RLS CAP
S87°W 64.97'



Signed by Carl T. Kiiskila
Surveyor's Michigan License No. 33981

Date 4-8-97