

SURVEY & REMONUMENTATION

APR 14 1998

LIBER 2 PAGE 82

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

15 Jan 1998 4:10:51 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES One

<u>BENZIE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>14W</u>	<u>H-9</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, CARL KIISKILA, in a field survey on JULY 9, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9								●					
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
H-9

G.L.O. "SET POST - BEECH 10 N38°W †, HEMLOCK 8 S41°E †, † THE DISTANCE TO THE BEARING AT THIS OR. SEC. CORNER WERE, THROUGH CARELESSNESS, OMITTED IN PUTTING DOWN THE NOTES". - NO EVIDENCE OF THIS POST OR BEARING TREES WAS FOUND. R. MAX HARRIS, PS #25845, SET 1/2" ROB BY PROPORTIONATE MEASUREMENT JUNE 1991 L.C.R.C. LIBER 1, PAGE 272.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-9
FOUND 1/2" REROD FITTING R. MAX HARRIS WITNESSES AND JUNE 1991 L.C.R.C.

Ratified by Peer Group
In accordance with P.A. 348
Chairman [Signature]
Date 12/7/1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
H-9

REPLACED FD 1/2" REROD W/4"x 3/8" CONC. MON W/BENZIE CO REMON PROGRAM BRASS CAP AND SET CARSONITE POST.

- 4"S. MAPLE N85°W 34.15'
- 126" BASSWOOD N40°W 33.63'
- 110"S. MAPLE N15°W 34.96'
- 110" IRONWOOD N20°E 35.33'
- 3"B. CHERRY S35°E 13.09'

† = PS, M. HARRIS 1991 WIT.

Signed by Carl T. Kiiskila
Surveyor's Michigan License No. 33981

Date 4-8-97

