

APR 14 1998

LIBER 2 PAGE 83

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

For corners in

BENZIE

(County)

Located in:

Corner Code #

1. Public Land Survey

T 27N R 14W

H-11

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling in Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

15 Jan 1998 4:11:05 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES one

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, CARL KIISKILA, in a field survey on OCTOBER 7, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-11

G.L.D. SET POST - 18" BEECH NO DISTANCE GIVEN AND 18" BEECH NO DISTANCE GIVEN. OLD SURVEY NOTES FROM SURVEYORS REC. NO 11, PAGES 100-101 SAYS "CEDAR POST 4"X 3' BLACK DIRT & CHARCOLE", SURVEYOR AND DATE UNKNOWN (DIST. ON MAP SHOWS COR. AT S.P. POSITION). R. MAX HARRIS, P.S. #25845, 1992 L.C.R.C. LIBER 1, PAGE 281 REESTABLISHED BY SINGLE PROPORTIONATE MEASUREMENT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-11

FOUND 1/2" IRON WITH R. MAX HARRIS CAP AND FITTING HIS WITNESSES.

Ratified by Peer Group
In accordance with P.A. 345

Chairman [Signature]

Date 7/24/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11

FD 1/2"x 18" REROD W/PS CAP, REPLACED W/4"x 36" CONC. MON W/BENZIE CD REMON BRASS CAP. DROVE ORANGE CARSONITE POST 1' SOUTH.

14°S.MAPLE N20°W 46.05' (FD NAIL & TAG NE SIDE)

7° BEECH N45°E 38.84' (DROVE NAIL & TAG SE SIDE)

8° S.MAPLE S40°E 26.13' (FD NAIL & TAG SW SIDE)

9°S.MAPLE(CLP 4) S40°W 18.50' (FD NAIL & TAG SE SIDE)

CTR OF E-W SAND TRAIL RD IS 6' NORTH.

‡ = PS, M.HARRIS 1992 WIT.

Signed by Carl T. Kiiskila

Date 4-8-97

Surveyor's Michigan License No. 33981

