

APR 14 1998

LIBER 2 PAGE 84

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
BENZIE COUNTY  
RECORDED

For corners in

BENZIE  
(County)

Located In:

Corner Code #

15 Jan 1998 4:11:20 PM  
MICHELLE R. GRAY  
REGISTER OF DEEDS  
# PAGES one

- |                                    |   |             |
|------------------------------------|---|-------------|
| 1. Public Land Survey              | T <u>27N</u> R <u>14W</u>                 | <u>H-13</u> |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
| 2. Property Controlling in Section | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
|                                    | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
| 3. Miscellaneous Property in Sec.  | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
|                                    | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, CARL T. KIISKILA, in a field survey on AUGUST 27, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13

G.L.O. SET POST - SUGAR 16, N17°E 19(12.5'); SUGAR 15 N40°W 40(26.4'). NO EVIDENCE OF G.L.O. POST OR BEARING TREES WAS FOUND. LAND SURVEYOR R. MAX HARRIS, PS #25845, JUNE 12, 1992 CERTIFICATE STATES HE SET THE 51/4 COR OF SECTION 34. BENZIE COUNTY ROAD COMMISSION SHOWS SIMILAR DISTANCES 1/2 MILE TO THE EAST AND WEST AS RECORDED BY R. MAX HARRIS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13

FOUND AND ACCEPTED A RR SPIKE AS SET BY P.S. R. MAX HARRIS.

Ratified by Peer Group  
In accordance with P.A. 345

Chairman [Signature]

Date 7/24/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13

FD SMALL RR SPIKE, REPLACED W/4" x 36" CONC MON W/BENZIE CO REMON PROGRAM BRASS CAP. CORNER IS IN LINE W/CTR B.TOP RD LOOKING NORTH, CTR GRAVEL RD TO EAST IS 14' N & CTR B.TOP RD WSW IS 6' NORTH.

#TEL. BOX POLE S59°W 72.03'

#36" S.MAPLE N63°E 77.82'

#28" S.MAPLE S70°E 43.85'

#POWER POLE S35°E 17.83'

FD 1 1/8" x 18" IRON ROD FOR N1/4 COR S-3, T26N-R14W S89°20'E 10.20'

FD RR SPIKE(RD P1) N00°09'E 6.4'

± PS, M.HARRIS 1992 WIT.

Signed by Carl T. Kiiskila

Date 4-8-97

Surveyor's Michigan License No. 33981

