

**SURVEY & REMONUMENTATION**

APR 14 1998

LIBER 2 PAGE 85

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BENZIE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 27N R 14W

I-6

T      R     

T      R     

T      R     

2. Property Controlling in Section

S     

T      R     

S     

T      R     

3. Miscellaneous Property in Sec.

S     

T      R     

S     

T      R     

STATE OF MICHIGAN  
BENZIE COUNTY  
RECORDED

15 Jan 1998 4:11:36 PM  
MICHELLE R. GRAY  
REGISTER OF DEEDS  
# PAGES One

Register of Deeds Stamp & File Number

4. Lot No.         , Recorded Plat         

5. Private Claims         

I, CARL KIISKILA, in a field survey on MAY 30, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15	●	14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-6

G.L.O. SET BEECH POST - 15" SUGAR MAPLE S78°W 20.5', 8" BEECH N87°E 8.6'. NO EVIDENCE OF THIS G.L.O. POST OR BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6

SET CORNER BY SINGLE PROPORTIONATE MEASUREMENT BETWEEN FOUND SECTION CORNER TO THE NORTH AND REESTABLISHED CORNER TO THE SOUTH.

Ratified by Peer Group  
In accordance with P.A. 345  
Chairman [Signature]  
Date 12/7/1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6

SET BENZIE CO. RENON MON. W/BRASS CAP AND CARSONITE POST  
12" TRI. MAPLE N70°W 25.38'  
4" IRONWOOD N10°W 10.01'  
7" W.PINE S30°E 27.42'  
8" W.PINE S20°W 31.09'



Signed by Carl T. Kiiskila  
Surveyor's Michigan License No. 33981

Date 4-8-97