

APR 14 1998

LIBER 2 PAGE 87

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

For corners in

BENZIE

Located in:

Corner Code #

(County)

1. Public Land Survey

T 27N R 14W I-B

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

15 Jan 1998 4:12:04 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES one

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, CARL KIISKILA, in a field survey on JULY 9, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-B

G.L.O. SET SUGAR MAPLE POST - BEECH 14, N83°E 19(12.5'). R. MAX HARRIS, P.S. #25845, 1991 L.C.R.C. LIBER 1, PAGE 271 SAID "G.L.O. CORNER POST & ACCESS. GONE. 1/2" IRON ROD SET PROPORTIONATE TO G.L.O. AS MEA. FROM WEST & PROPORTIONATE TO G.L.O. AS MEA. FROM SOUTH PLATTE TWP. LINE TO NORTH LINE OF SEC. 15-27-14 (FOWLER ROAD)".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-B

FOUND 1/2" REROD WITH M. HARRIS RLS CAP. REROD FITS HIS PROPORTIONATE MEASUREMENTS TO THE N, S & W WELL.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 12/18/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-B

REPLACED FD 1/2" REROD W/4"x 36" CONC. MON W/BENZIE CO REMON PROGRAM BRASS CAP AND SET CARSONITE POST.

#3" IRONWOOD N10°W 6.45'

3"B. CHERRY S60°E 41.51'

#6" TW. MAPLE S25°W 47.78'

4"B. CHERRY S65°W 29.11'

X= PS, M. HARRIS 1991 MIT.



Signed by Carl T. Kiiskila
Surveyor's Michigan License No. 33981

Date 4-8-97