

APR 14 1998

LIBER 2 PAGE 89

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
BENZIE COUNTY  
RECORDED

15 Jan 1998 4:12:30 PM  
MICHELLE R. GRAY  
REGISTER OF DEEDS  
# PAGES one

For corners in

| BENZIE<br>(County)                    | Located In:                               | Corner Code # |
|---------------------------------------|---|---------------|
| 1. Public Land Survey                 | T <u>27N</u> R <u>14W</u>                 | <u>I-10</u>   |
|                                       | T <u>    </u> R <u>    </u>               | <u>    </u>   |
|                                       | T <u>    </u> R <u>    </u>               | <u>    </u>   |
|                                       | T <u>    </u> R <u>    </u>               | <u>    </u>   |
| 2. Property Controlling<br>in Section | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u>   |
|                                       | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u>   |
| 3. Miscellaneous<br>Property in Sec.  | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u>   |
|                                       | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u>   |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, CARL KIISKILA, in a field survey on SEPTEMBER 9, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    | A | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  |   | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  |   | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  |   | 16 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  |   | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 |   | 30 |   | 29 |   | 28 |   | 27 | ● | 26 |   | 25 |   |
| 11 |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 |   | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |   |    |   |    |   |    |   |    |   |    |   |    |   |

A. Description of original monument and accessories and/or subsequent restoration:

I-10

G.L.O. SET POST - 14" SUGAR MAPLE N53°W 29.0' AND 8" SUGAR MAPLE S43°E 2.0'. NO EVIDENCE OF THIS G.L.O. POST OR BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10

REESTABLISHED THE CORNER BY SINGLE PROPORTIONATE MEASUREMENT, MIDWAY AND ON LINE BETWEEN FOUND CORNERS TO THE NORTH AND SOUTH.

Validated by Peer Group  
In accordance with P.A. 346

Chairman [Signature]  
Date 7/24/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10

SET 4"x 36" CONC MON W/BENZIE CO REMON PROGRAM  
BRASS CAP AND SET CARSONITE POST.  
11" W.PINE N80°W 59.71'  
4" MAPLE N15°E 28.83'  
13" B.CHERRY S40°E 25.44'  
14" TW.B.CHERRY S60°W 72.54'  
CTR OF N-S CROOKED TRAIL IS 16' WEST.



Signed by Carl T. Kiiskila  
Surveyor's Michigan License No. 33981

Date 4-8-97