

SURVEY & REMONUMENTATION

APR 14 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 91

For corners in

<u>BENZIE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>14W</u>	<u>I-12</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
 BENZIE COUNTY
 RECORDED

15 Jan 1998 4:12:56 PM
 MICHELLE R. GRAY
 REGISTER OF DEEDS
 # PAGES One

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL T. KIISKILA, in a field survey on AUGUST 27, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-12
 G.L.O. - SET SUGAR POST FOR DR. POST; BEECH 6 S71°W 18 (11.9'), SUGAR 12 S78°E 10 (6.6'). OLD SURVEY NOTES FD AT BENZIE CO. RD. COMM. FOR S-34 CALLS FOR 1" PIPE BETWEEN 2 OLD STAKES.

Ratified by Peer Group
 In accordance with P.A. 345

Chairman [Signature]

Date 7/24/96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-12
 MI DNR SURVEY CREW ON 7-1-93 FOUND OLD 1" PIPE BURIED 1/2', 3' WEST OF CTR. OLD N-S LANE; OLD N-S WOVEN WIRE FENCE IS 25'+/-, EAST. PIPE FITS SURVEY DATA PER OLD NOTES FD. AT B.C.R.C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12
 FD OLD BATTERED 1"x 29" PIPE, REPLACED W/4"x 36" CONC. MON. W/BCRP BRASS CAP AND SET CARSONITE POST.
 22" S.MAPLE N30°W 14.98'
 5" S.MAPLE N15°W 27.09'
 33" S.MAPLE N15°E 55.78'
 14" S.MAPLE N75°E 22.11'
 OLD 3-STRAND CROOKED BARB/WIRE FENCE W'LY IS 50'+/- 12' NORTH.



Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-8-97