

APR 14 1998

LIBER 2 PAGE 92

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

For corners in

BENZIE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 27N R 14W

I-13

T R

T R

T R

T R

2. Property Controlling in Section

S

T R

S

T R

3. Miscellaneous Property in Sec.

S

T R

S

T R

15 Jan 1998 4:13:09 PM
NICHELLE R. GRAY
REGISTER OF DEEDS
PAGES One

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, CARL T. KIISKILA, in a field survey on OCTOBER 7, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-13

U.S. 6.L.O. - SET POST COR SEC'S 34 & 35; BEECH 11 N50W 33.7', BEECH 8 N58E 24.4', OLD NOTES FD AT BENZIE CO. RD. COMM CALLS FOR "IRON PIPE 1 1/4" PIPE".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13

ON 11-5-92 DNR SURVEY CREW FOUND 1/2" REROD W/M.HARRIS PS CAP; ON 10-7-96 DNR CREW FD 1/2" REROD W/PS CAP OVER OLD 1 1/2" WELL SCREEN AND REPLACED W/BCRP MON.

Ratified by Peer Group
In accordance with P.A. 345

Chairman [Signature]

Date 7/24/1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13

FD 1/2"x 18" REROD W/PS CAP & BOTTOM 13"x 1 1/2" OLD WELL SCREEN, REPLACED W/4"x 36" CONC. MON W/BCRP BRASS CAP. CTR OF E-W GRAVEL RD. IS 9' SOUTH, CTR OF GRAVEL RD TO SOUTH IS 5' EAST.

FD BENZIE CO MON(INE S-3, T26N-R14W S88 58'E 14.77'

13"S.MAPLE N60°W 43.54'(NAIL & TAG NE SIDE)

16" S.MAPLE N35°E 47.69'(NAIL & TAG SE SIDE)

10" MAPLE S45°E 80.66'(NAIL & TAG NE SIDE)

18" MAPLE(CLP-4) S30°W 48.25'(NAIL & TAG NW SIDE)

SET CARSONITE POST W/LOC TAG NORTH 33'. SW COR E1/2 OF SE1/4 OF SE1/4

OF S-34, SET 5/8"x 34" REROD W/PS CAP N89°20'W 659.64'

Signed by Carl T Kiiskila

Date 4-9-97

Surveyor's Michigan License No. 33981

