

APR 14 1998

LIBER 2 PAGE 93

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

15 Jan 1998 4:13:21 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES one

For corners in

BENZIE

(County)

Located in:

Corner Code #

1. Public Land Survey

T	<u>27N</u>	R	<u>14W</u>	<u>J-7</u>
T	_____	R	_____	_____
T	_____	R	_____	_____
T	_____	R	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

I, CARL KIISKILA, in a field survey on DECEMBER 19, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
J-7

6.L.O. SET POST - 16" SUGAR MAPLE S64°E 11.2', 12" BEECH N48°W 28.4'. NO EVIDENCE OF THIS 6.L.O. POST OR BEARING TREES WAS FOUND.

Ratified by Peer Group
in accordance with P.A. 345
Chairman John B. [Signature]
Date 12/7/1995

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-7
REESTABLISHED 5/4 CORNER OF S-14 BY SINGLE PROPORTIONATE MEASUREMENT MIDWAY AND ON LINE BETWEEN REESTABLISHED CORNERS TO THE EAST AND WEST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-7
SET BENZIE CO. REMON. MON AND CARSONITE POST.
18" TW. MAPLE N40°W 31.02'
8" R. PINE S50°E 80.71'
11" B. CHERRY S10°E 40.64'
5" MAPLE S65°W 49.44'



Signed by Carl T. Kiiskila
Surveyor's Michigan License No. 33981

Date 4-8-97