

SURVEY & REMONUMENTATION

APR 14 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE LIBER 2 PAGE 94
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|------------------------------------|---------------------------|---------------|
| <u>BENZIE</u> (County) | Located in: | Corner Code # |
| 1. Public Land Survey | T <u>27N</u> R <u>14W</u> | <u>J-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
 BENZIE COUNTY
 RECORDED

15 Jan 1998 4:13:34 PM
 MICHELLE R. GRAY
 REGISTER OF DEEDS
 # PAGES one

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL KIISKILA, in a field survey on JULY 8, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-9

G.L.O. SET POST - 16" BEECH S15°W 26.4' AND 16" SUGAR MAPLE N45° E 45.5'. NO EVIDENCE OF THIS G.L.O. POST OR BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9

REESTABLISHED CORNER BY SINGLE PROPORTIONATE MEASUREMENT BETWEEN FOUND CORNER TO THE WEST AND REESTABLISHED CORNER TO THE EAST.

Ratified by Peer Group
 In accordance with P.A. 345

Chairman [Signature]

Date 12/18/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9

SET 4"x 36" CONC. MON W/BENZIE CO REMON PROGRAM
 BRASS CAP. SET CARSONITE POST.
 12" B. CHERRY N75°W 24.06'
 6" B. CHERRY N25°W 42.59'
 7" TW. B. CHERRY N55°E 49.14'
 9" B. CHERRY S30°E 7.2B'
 N-S WINDING TRAIL IS 180° +/- 15' NORTH.



Signed by Carl T Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-8-97