

SURVEY & REMONUMENTATION

APR 14 1998

LIBER 2 PAGE 97

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
For corners in

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

15 Jan 1998 4:14:54 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES one

<u>BENZIE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>14W</u>	<u>K-7</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, CARL KIISKILA, in a field survey on JULY 3, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-7

G.L.D. SET POST - 8" SUGAR MAPLE S53°W 19.8', 9" SUGAR MAPLE N45°E 9.9'. NO EVIDENCE OF THIS G.L.D. POST OR BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-7

REESTABLISHED CORNER BY DOUBLE PROPORTIONATE MEASUREMENT BETWEEN FOUND CORNERS 1 MILE TO THE NORTH, EAST AND WEST AND 2 MILES TO THE SOUTH.

Ratified by Peer Group
In accordance with P.A. 345

Chairman [Signature]
Date 12/7/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7

SET 4"x 36" CONG. MON W/BENZIE CO. REMON PROGRAM
BRASS CAP AND SET CARSONITE POST.
3" MAPLE N50°W 8.77'
4" TW. MAPLE N50°E 19.50'
14" B. CHERRY S75°E 20.78'
8" MAPLE S10°E 10.78'



Signed by Carl T. Kiiskila
Surveyor's Michigan License No. 33981

Date 4-8-97