

APR 14 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**LIBER 2 PAGE 99**

For corners in

BENZIE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 27N R 14W K-9  
 T     R          
 T     R          
 T     R          
 T     R        

2. Property Controlling in Section

S     T     R          
 S     T     R          
 S     T     R          
 S     T     R        

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
BENZIE COUNTY  
RECORDED

15 Jan 1998 4:15:33 PM  
MICHELLE R. GRAY  
REGISTER OF DEEDS  
# PAGES one

Register of Deeds Stamp & File Number

I, CARL KIISKILA, in a field survey on JULY 8, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-9

G.L.O. SET BEECH POST - 12" BEECH N35°E 20.5' AND 14" SUGAR MAPLE S38°W 19.8'. NO EVIDENCE OF G.L.O. POST OR BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9

REESTABLISHED CORNER BY DOUBLE PROPORTIONATE MEASUREMENT BETWEEN FOUND CORNERS 1 MILE TO THE WEST AND SOUTH, AND 2 MILES TO THE NORTH AND EAST.

Ratified by Peer Group  
In accordance with P.A. 345  
Chairman Col. B. [Signature]  
Date 12/18/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9

SET 4"x 36" CONC. MON. W/BENZIE CO. REMON PROGRAM  
 BRASS CAP. SET CARSONITE POST.  
 12" MAPLE (CLP-4) N50°W 9.75'  
 4" S. MAPLE N20°E 12.64'  
 7" TW. S. MAPLE S35°E 11.31'  
 4" BEECH S15°W 19.91'



Signed by Carl T. Kiiskila  
 Surveyor's Michigan License No. 33981

Date 4-10-97