

**SURVEY & REMONUMENTATION**

APR 14 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 100

For corners in

BENZIE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 27NR 14W

K-10

T      R     

T      R     

T      R     

2. Property Controlling in Section

S      T      R     

S      T      R     

3. Miscellaneous Property in Sec.

S      T      R     

S      T      R     

STATE OF MICHIGAN  
BENZIE COUNTY  
RECORDED

15 Jan 1998 4:15:50 PM  
MICHELLE R. GRAY  
REGISTER OF DEEDS  
# PAGES One

Register of Deeds Stamp & File Number

4. Lot No.         , Recorded Plat         

5. Private Claims         

I, CARL KIISKILA, in a field survey on SEPTEMBER 9 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-10

G.L.O. SET POST - 12" BEECH N35°E 20.5' AND 14" SUGAR MAPLE S38°W 19.8'. NO EVIDENCE OF THIS G.L.O. POST OR BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10

REESTABLISHED THE CORNER BY SINGLE PROPORTIONATE MEASUREMENT, MIDWAY AND ON LINE BETWEEN FOUND CORNERS TO THE NORTH AND SOUTH.

Ratified by Peer Group

In accordance with P.A. 345

Chairman [Signature]

Date 7/24/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10

SET 4" x 36" CONC MON W/BENZIE CD REMON PROGRAM BRASS CAP AND CARSONITE POST.

29" TW. S. MAPLE N85°W 79.64'

3" B. CHERRY (CLP) N10°E 15.64'

2" B. CHERRY EAST 15.32'

2" TW. B. CHERRY S45°E 14.48'

WINDING SAND TRAIL NE - SW IS N45°W 114' +/- 6'.



Signed by Carl T. Kiiskila

Date 4-8-97

Surveyor's Michigan License No. 33981