

**SURVEY &
REMONUMENTATION**

APR 14 1998

LIBER 2 PAGE 101

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BENZIE

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|------------|-------|
| 1. Public Land Survey | T | <u>27N</u> | R | <u>14W</u> | K-11 |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

15 Jan 1998 4:16:07 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES One

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, CARL KIISKILA, in a field survey on AUGUST 15, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-11

G.L.O. SET HEMLOCK POST - 14" SUGAR MAPLE S29°W 25.1' AND 12" BEECH N13°E 13.2'. R. MAX HARRIS, RLS #25845, FOUND 2" IRON PIPE PER JUNE 1991 CERTIFICATE. MICH. DNR FEB. 1993 FOUND 2" PIPE FITTING R. MAX HARRIS DISTANCES TO WEST.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-11

FOUND 1 1/2" IRON PIPE (PREVIOUSLY CALLED A 2" PIPE) 5' NORTH OF E-W TRAIL ROAD AND ON CTR TRAIL ROAD TO SOUTH. THE 1 1/2" (2") PIPE FITS R. MAX HARRIS RECORDED DISTANCE WEST, TO THE SW CORNER OF SECTION 26.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 12/24/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11

FD OLD 1 1/2" x 30" PIPE (PREVIOUSLY CALLED A 2" PIPE), REPLACED W/4" x 36" CONC MON W/BENZIE CO REMON PROGRAM BRASS CAP.
11" TW.S. MAPLE N50°W 63.22'
7" R. PINE N25°E 58.17'
24" BEECH N70°E 68.08'
9" R. PINE S50°E 52.67'
SET CARSONITE POST W/LOC. TAG NORTH 33'



Signed by Carl T. Kiiskila
Surveyor's Michigan License No. 33981

Date 4-8-97