

SURVEY & REMONUMENTATION

APR 14 1998

LIBER 2 PAGE 104

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
For corners in

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

15 Jan 1998 4:16:46 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES ONE

| | | |
|------------------------------------|---|---------------|
| <u>BENZIE</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>27N</u> R <u>14W</u> | <u>L-11</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, CARL KIISKILA, in a field survey on AUGUST 15, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-11
G.L.D. SET BEECH POST - 12" BEECH S73°E 9.2' AND 8" BEECH N43°W 7.9'. NO EVIDENCE OF THIS G.L.D. POST OR BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11
REESTABLISHED THE CORNER BY SINGLE PROPORTIONATE MEASUREMENT, MIDWAY AND ON LINE BETWEEN FOUND CORNER TO THE WEST AND REESTABLISHED CORNER TO EAST.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 7/24/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11
SET 4"x 36" CONC MON W/BENZIE CO REMON PROGRAM BRASS CAP AND CARSONITE POST.
6" B.CHERRY N30°W 46.99'
13" R.PINE N10°E 40.98'
6" TW.B.CHERRY S85°E 16.88'
8" TW.B.CHERRY S35°W 57.63'
CTR E-W SAND TRAIL IS 15' NORTH
OLD E-W FN REMAINS ON GROUND IS 22'+/- 3' SOUTH.



Signed by Carl T. Kiiskila
Surveyor's Michigan License No. 33981

Date 4-8-97