

SURVEY & REMONUMENTATION

APR 14 1998

LIBER 2 PAGE 105

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BENZIE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 27N R 14W M-9

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

15 Jan 1998 4:17:00 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES one

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, CARL KIISKILA, in a field survey on JULY 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-9

G.L.D. SET POST - 16" BEECH N41°E 6.6', 9" BEECH S34°E 20.5', 10" BEECH N57°W 12.5' AND 12" BEECH S62°W 15.2'. NO EVIDENCE OF THIS G.L.D. POST OR BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9

IT WAS DETERMINED TO RESTORE THE LOST CORNER BY DOUBLE PROPORTIONATE MEASUREMENT AS OPPOSED TO STRICT SINGLE PROPORTIONATE METHOD WHICH IS THE OPINION OF MICHIGAN DEPARTMENT OF NATURAL RESOURCES SURVEYORS THAT THE 1850 (GLO) MEASUREMENTS WERE MORE RELIABLE IN FOUR CARDINAL DIRECTIONS THAN A STRAIGHT LINE BETWEEN CONTROLLING CORNERS 3 MILES APART TO THE NORTH AND SOUTH. REESTABLISHED THE SE COR OF SEC 24 BY DOUBLE PROPORTIONATE MEASUREMENT BETWEEN FOUND CORNERS 1 MILE TO THE NORTH AND EAST, AND 2 MILES TO THE SOUTH AND WEST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9

SET 4"x 36" CONC. MON W/BENZIE CO REMON PROGRAM
BRASS CAP AND CARSONITE POST.

6" MAPLE N50°W 25.22'
11" BEECH N10°E 16.32'
18" R. MAPLE S55°E 4.06'
21" R. MAPLE S16°W 25.29'

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 12/18/95



Signed by Carl T Kiiskila
Surveyor's Michigan License No. 33981

Date 4-8-97