

SURVEY & REMONUMENTATION

APR 14 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE LIBER 2 PAGE 63
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
BENZIE
 (County)

Located In: Corner Code #

1. Public Land Survey

14W
 T 27N R ~~33E~~ M-10
 T R
 T R
 T R
 S T R
 S T R
 S T R
 S T R

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

STATE OF MICHIGAN
 BENZIE COUNTY
 RECORDED
 15 Jan 1998 4:05:07 PM
 MICHELLE R. GRAY
 REGISTER OF DEEDS
 # PAGES ONE
 Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, CARL KIISKILA, in a field survey on JUNE 27, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 A-10

G.L.D. SET POST - 10" SUGAR MAPLE N63°E 19.1' AND 9" HEMLOCK S38°W 19.8'. NO EVIDENCE OF THIS G.L.D. POST OR BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 A-10

REESTABLISHED CORNER BY SINGLE PROPORTIONATE MEASUREMENT BETWEEN REESTABLISHED CORNERS TO THE NORTH AND SOUTH.

Ratified by Peer Group
 In accordance with P.A. 345
 Chairman [Signature]
 Date 12/18/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A-10

SET 4"x 36" CONC NON W/BENZIE CO REMON PROGRAM BRASS CAP AND SET CARSONITE POST.
 6" S. MAPLE N20°W 37.46'
 14" R. MAPLE N35°E 9.62'
 7" TRI. S. MAPLE S50°E 31.11'
 7" BEECH S87°W 43.13'



Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-9-97