

SURVEY & REMONUMENTATION

APR 14 1998

LIBER 2 PAGE 64

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

For corners in

BENZIE

(County)

Located In:

Corner Code #

1. Public Land Survey

14w
T 27N R M-12
T _____ R _____
T _____ R _____
T _____ R _____
T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

2. Property Controlling
in Section
3. Miscellaneous
Property in Sec.

15 Jan 1998 4:05:21 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES one

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, CARL KIISKILA, in a field survey on JUNE 25, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-12

G.L.D. SET POST - 24" SUGAR MAPLE N40°E 40.3' AND 7" ELM S56°W
8.6'. NO EVIDENCE OF THIS G.L.D. POST OR BEARING TREES WAS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-12

REESTABLISHED CORNER BY SINGLE PROPORTIONATE MEASUREMENT BETWEEN REESTABLISHED CORNERS TO THE NORTH AND SOUTH.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 12/18/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12

SET 4"x 36" CONC MON W/BENZIE CO REMON PROGRAM BRASS CAP AND CARSONITE POST.
9" S. MAPLE N30°W 9.76'
9" B. CHERRY N40°E 16.45'
11" S. MAPLE S30°E 19.17'
11" BASSWOOD S20°W 6.54'



Signed by Carl T. Kiiskila
Surveyor's Michigan License No. 33981

Date 4-9-97