

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Benzie Located In _____ Corner Code # _____
 (County)

1. Public Land Survey T _____ R _____
 T _____ R _____

2. Property Controlling in Section S 11 T 27N R 14W 9
 S _____ T _____ R _____

3. Miscellaneous Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Aug. 26, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

9 – Unrecorded Survey – Wm. B. Batzer, Jr. –
 File No. 87178 (1987) - 1/2" x 24" iron rod set

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

9 – CE 1/16, Sec. 11 – Fd. 1/2" x 24"
 Capped iron #13026. Fits Sec.
 Sub. per previous DNR Survey
 Work by C. F. Roser. 1/2" capped
 Iron rebar accepted as the best
 available evidence of the position
 of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

9 – Replaced 1/2" x 24" capped iron rebar #13026 w/ 2" Alum.
 Cap "stamped" on 5/8" x 34" iron rebar.
 Set blue carsonite post 1' NW.
 Fd. Steel Fence post on SE side as guard
 N67°E 15.83' to set N & T in S. Side 4" S. Maple
 S32°E 30.64' to set N & T in E. side 8" S. Maple
 S70°E 8.04' to set N & T in N. side 5" S. Maple
 S13°W 23.42' to set N & T in E. side 32" Beech



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 9/23/2003