

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*George J. Mitchell*  
11-09-95  
For corners in  
BERRIEN  
(County)

Located In: Corner Code #

NORTHWEST CORNER, SECTION 4, COLOMA TOWNSHIP

1. Public Land Survey T 3 S R 17 W E-1  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

RECORDED

Nov 29 3 38 PM '95

*George J. Mitchell*  
REGISTER OF DEEDS  
BERRIEN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, George J. Mitchell in a field survey on November 15, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

SURVEY &  
MONUMENTATION  
MAR 27 1996  
COMMISSION

E-1

SEE SHEET 2 OF 2



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1

FOUND 1/4" IRON INSIDE OF A 1" PIPE WITH STONE ON TOWNLINE FROM CORNER HISTORY AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

THIS CORNER WAS APPROVED BY THE BERRIEN COUNTY SURVEYORS PEER GROUP ON NOVEMBER 9, 1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED IRON AND PIPE WITH BERRIEN COUNTY STANDARD 36" PIPE AND BRACE CAP WITH DRILL HOLE AND THE NUMBER 19618 STAMPED ON TOP. PIPE WAS SET 12" BELOW GRAVEL ROAD SURFACE.

WITNESS TAG & NAIL SET IN SE SIDE OF POWER POLE	AZ. 320°	42.86'
WITNESS TAG & NAIL SET IN NORTH SIDE OF 50" COTTONWOOD	AZ. 265°	109.60'
WITNESS TAG & NAIL SET IN EAST SIDE OF POWER POLE	AZ. 185°	165.40'
WITNESS TAG & NAIL SET IN NORTH SIDE OF 8" BOXELDER	AZ. 120°	142.95'
SOUTHEAST CORNER, SECTION 32, T2S, R17W	AZ. 90°	146.60'

SHEET 1 OF 2

Signed by George J. Mitchell Date November 15, 1995  
Surveyor's Michigan License No. 19618

GOVERNMENT CORNER HISTORY

E1, T3S, R17W

NORTHEAST CORNER OF SECTION 5  
TOWN 3 SOUTH, RANGE 17 WEST, COLOMA TOWNSHIP

E-1

APRIL 1827  
WILLIAM BROOKFIELD

NORTH BETWEEN SEC. 4 & 5  
40.00 SET 1/2 MILE POST  
78.40 INTERSECTED N BOUNDARY 2.22 LINK  
WEST OF POST - SET CORNER  
BEECH 14 S4E 58  
BEECH 14 S16W 25

JOHN HOWARD (NO DATE)

IRON  
2.22 CHAINS WEST OF V.B. CORNER

1971 STEFAN

FD IRON PIPE

1975 ROAD COMM.

FD IRON  
P.P. N50W - 42.73  
CL ROAD IS EAST 68'  
T. POLE S60W 69.12  
T. POLE S70E 88.59 GONE 1995

1975 WIGHTMAN

FD. IRON PIPE  
P.P. N45W 42.4  
P.P. S75W 68.82  
CONC. POST S50E 76.37 GONE 1995

1986 WIGHTMAN

FD. IRON  
P. POLE N50W 42.8  
GUARD POST S10E 17.9 GONE 1995  
P.P. S70E 88.95

1990 MITCHELL

FD. 1/4" IRON PIN INSIDE 3/4" GAS PIPE  
POWER POLE NW 43.20  
POWER POLE SW 69.30  
CL N-S RD EAST 68.0'  
SE COR. SEC. 32 T2S, R17W - EAST 146.6'

MITCHELL  
10/19/95

FD. 1/4 IRON PIN INSIDE 1" PIPE  
POWER POLE N50W 42.85'  
CENTER OF ROAD EAST 68.0'  
POWER POLE SW 69.30'  
SE COR SEC 32 2S, 17W EAST 146.60'