



**GOVERNMENT CORNER HISTORY**

**EAST QUARTER POST OF SECTION 10  
TOWN 3 SOUTH, RANGE 17 WEST**

**I-4**

- 1830 WILLIAM BROOKFIELD  
40.00 1/2 MILE POST  
BEECH 14 S 31 1/2 E 22  
DO 6 N 74 1/2 W 10
- NO DATE A.W. HOWARD - OLD NOTES  
IRON W/ 3" HEAD  
12" MAPLE S 23° E 65.62'  
28" ELM S 31° W 45.44'  
8" HICKORY N 45° 30' W 39.82'
- NO DATE J.H. DEWEY  
MON BOX - STONE  
POST W 33.0'  
16" ELM S 70° W 28.0'  
8" MAPLE S 30° E 65.5'  
P.POLE S 50° W 41.70'  
P.POLE N 45° E 51.00'  
P.POLE S 60° E 73.34'
- 1971 NEIL R. BERNDT - RECORDED SURVEY LIBER ???, PAGE ???  
MON BOX  
P.POLE B115 -106 SW 42.0'  
T.P. 212 - 23 NE 51.5'  
P.POLE B116-10 SE 73.8'
- 1982 JOHN KAMER - L.C.R.C. L. 2, P.380  
FOUND MICH DEPT OF STATE HWY BRASS  
PLATE IN MON BOX  
P.K. NAIL IN POWER POLE N 60° E 51.05'  
P.K. NAIL IN 16" ELM N 50° W 34.87'  
P.K. NAIL IN P.POLE S 40° W 41.68'
- 1986 J. KAMER  
FOUND STATE MON BOX  
P. POLE S 50° W 41.84'  
16" OAK N 60° W. 35.09'  
P. POLE N 45° E 50.87'
- 1991 JOHN HUNT  
FD STANDARD DISK MARKER IN MON BOX  
IN LINE WITH CL OF ROADS NORTH-SOUTH & EAST  
N 45° E 51.00' P.K. NAIL SE'LY FACE OF POLE  
S30° W 41.70' P.K. NAIL NORTH FACE OF POLE  
S70° E 73.20' P.K. NAIL SE FACE OF POLE  
N75° W 34.65' P.K. NAIL SOUTH BASE 18" DIA OAK
- 1997 DONALD R. PITTS, JR., MITCHELL SURVEYS, INC.  
FD STATE OF MICH MON IN MON BOX  
CL 12" HICKORY N 40° W 39.5'  
P.K. NAIL NW SIDE P. POLE S 50° W 41.69'  
P.K. NAIL SE SIDE P. POLE N 45° E 51.05'  
P.K NAIL SW SIDE P. POLE S 60° E 73.14'  
CL 24" ELM N 50° W 34.8'

REMONUMENTATION

NOV 21 1997

COMMISSION