

RAISED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

[Signature]
5-16-00
Filing Requirement of Act 74, Mich. P.A. 1970
For corners in

**BERRIEN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

BERRIEN Located In: _____ Corner Code # M-11
(County)

- | | | | | | |
|------------------------------------|---|-----|---|------|------|
| 1. Public Land Survey | T | 3 S | R | 17 W | M-11 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | T | R | | |
| | S | T | R | | |
| 3. Miscellaneous Property in Sec. | S | T | R | | |
| | S | T | R | | |
4. Lot No. _____, Recorded Plat _____ 5.
Private Claims _____

10/20/00 111#4516 A66
CORNER \$7.00
10/20/00 111#4516 A66
STATE REMON FEE \$2.00

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, V.J. Strebs, in a field survey on SEPT 21, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 WILLIAM BROOKFIELD, D.S.
SET CORNER TO SECTIONS 24 AND 25
5" WHITE OAK NORTH 24 LINKS
7" MAPLE S 641/3°W 83 LINKS
(SUPPLEMENTAL ENTRY CORNER TO SECS. 19 AND 30, T3S, R16W
40 LINKS (26.40') NORTH)
- 1971 SOUTHWEST SURVEY AND ENGINEERING CO.
(MON. BOX)
CONC. HEADWALL S 75 °W 62.6'
STREET SIGN N 45°E 48.0'
T.P. S 40°E 129.5'
- 1980 BERRIEN COUNTY ROAD COMMISSION
(MON. BOX)
TEL RISER BOX S 40 °W 46.4'
C/L STREET SIGN POLE N 40 ° E 48.4'
NAIL IN GUARD POST S 85 ° E 26.4'
- 1997 WIGHTMAN AND ASSOCIATES
(MICH. BRASS CAP IN MON. BOX)
N.E. COR HEADWALL N 70 ° W 71.38'
S.COR. SIGN N 60°W 55.39'
TOP C/L TEL. RISER BOX S 40 ° W 46.88'
S.W. COR. SEC. 30-3-16 NORTH 26.25'

**SURVEY &
REMONUMENTATION**

JAN 31 2001

SECTION

RECORDED
 00 OCT 20 PM 3:34
 BERRIEN COUNTY, MICHIGAN
 REGISTER OF DEEDS
 SERVICE CENTERWAY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND MICHIGAN BRASS CAP IN MONUMENT BOX

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- REMOVED BRASS CAP, RESET WITH 1" X 3' IRON PIPE W/ B.C.R.P. BRASS CAP STAMPED 26469, 2000
- TOP CENTER OF TEL. RISER BOX S 45 ° W 46.85'
- TOP CENTER OF CONCRETE STORM STRUCTURE S 70 °W 73.25'
- TOP CENTER OF CONCRETE STORM STRUCTURE N 60 °W 88.20'
- S.W. COR. SEC. 30-3-16 NORTH 26.27'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *[Signature]*
Surveyor's Michigan License No. 26469

Date 19 OCT 2000

