

RATIFIED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

08/24/94

111#1725 A33
CORNER \$7.00
111#1725 A33
STATE REMON FEE \$2.00

BERRIEN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
BERRIEN COUNTY MICHIGAN
Barbara Thackeray

AUG 24 10 54 AM '94

RECORDED

For corners in Berrien
(County)

Located In:	Corner Code #
T <u>3S</u> R <u>18W</u>	<u>L-2</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

- Lot No. _____, Recorded Plat _____
- Private Claims _____

I, V.J. Strebs, in a field survey on 28 July, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1883 - Luther Hemingway
Set Post with Stones & Crockery at the intersection of Quarter lines

1985 - Berrien County Road Commission
(Iron over stone)
P.K. Nail in Power Pole - N20°E - 32.1'
20" Cherry-N40°W-30.4'
P.K. Nail in Power Pole - S40°W - 35.40'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3 irons and stones over bricks around remains of wood post

SURVEY & REMONUMENTATION
 SEP 15 1994
COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1"X3FT iron pipe with B.C.R.P. Brass cap in Place of Wood post remains, put stones around iron and set monument box above those, approx. one foot below gravel road surface.
Nail & Witness Tag in 24" Cherry - N35°W - 31.70'
Nail & Witness Tag in Power Pole (B-102-53) - S45°W - 35.23'
Nail & Witness Tag in Power Pole (B-102-99) - N30°E - 32.35'
Nail & Witness Tag in Corner Fence Post - S45°E - 57.70'



Signed by *V.J. Strebs*
Surveyor's Michigan License No. 26469

Date 5 August 1994