

RATIFIED BY THE BERRIEN COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 347 OF 1990

08/24/94

111#1725

A33

CORNER

\$7.00

08/24/94

111#1725

A33

STATE REMON FEE \$2.00

BERRIEN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
BERRIEN COUNTY MICHIGAN
Registrar Hemingway

AUG 24 10 54 AM '94

RECORDED

For corners in
Berrien
(County)

Located In: Corner Code =#

1. Public Land Survey	T	3S	R	18W	M-2
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, V.J. Strebs, in a field survey on 28 July, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 - William Brookfield, G.L.O.
24" Beech @ Cor.
- 1883 - Luther Hemingway
No Witnessess

Berrien County Road Commission (Stone)
Electric Pole - S20°W - 119.4'
6" End Pear - N.E. - 35.5' 6" End Pear - S.E. - 32.9'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Stone & Iron in Monument Box

**SURVEY &
REMONUMENTATION**

 SEP 15 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Pulled Iron & Stone
- Set 1" x 3 FT Iron Pipe with B.C.R.P. Brass Cap in Monument Box
- Nail & Witness Tag in Corner Fence Post - S70°E - 36.60'
- Nail & Witness Tag in Power Pole (B 103-36) - S55°E - 174.35'
- B.C.R.P. Brass Cap in Monument Box - South - 45.80'
- 1" Iron Pipe - North - 13.95'
- Nail & Witness Tag in Power Pole (B-102-36) - S15°W - 121.95'



Signed by *V.J. Strebs*
Surveyor's Michigan License No. 26469

Date 5 August 1994