

RAISED BY THE BERRIEN COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 445 OF 1990

RECORDED

Berrien County Remonumentation Program
LAND CORNER RECORDATION CERTIFICATE

00 NOV - 8 PM 12:51

SERVICE TRETHERWAY
REGISTER OF DEEDS
BERRIEN COUNTY, MICHIGAN

11/08/00 111#6048 A66
CORNER \$7.00
11/08/00 111#6048 A66
STATE REMON FEE \$2.00

Register of Deeds Stamp & File
Number

for corners in

Berrien (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4S</u> R <u>17W</u>	<u>C-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Alan K. Bartlett, in a field survey on March 29, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827- WM. BROOKFIELD, DEPUTY SURVEYOR; WEST ON SOUTH SIDE OF SECTION 32 80.00 CHAINS SET CORNER TO SECTIONS 31 & 32. WITNESSES: N37.5°E 13 LINKS 12" LYNN, N37.5W 29 LINKS 6" BEECH
- 1875- THOMAS LAVE, COUNTY SURVEYOR; BEGAN SOUTHEAST CORNER SECTION BEARINGS GONE. FOUND ROOTS TO LYNN TO AGREE WITH NOTES. NOTHING MORE WAS FOUND. PUT IN STONE 15" LONG NEW BEARINGS: N89°E 34 LINKS 10' BLACK WALNUT, N21.5°W 10 LINKS 6" W. WALNUT
- 1972± ALTON HOWARD; 17.82' JOG, 1/2 MILE DISTANCE NORTH TO C-12 =2653.72'
- 1989- WIGHTMAN & ASSOCIATES, J. KAMER; SE CORNER STONE (HIGH POINT). WITNESSES: NORTH 9.52' SET PK IN POWER POLE, S50°W 71.57' SET PK IN POWER POLE, WEST 22.5' CENTERLINE OF ROAD

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND IRON PIPE OVER STONE, 6' EAST OF ROAD PAVEMENT.
THIS CORNER APPROVED BY THE BERRIEN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
REMOVED STONE, SET CONCRETE MONUMENT WITH BRASS CAP (MARKED 2000 & 35988)
THIS CORNER ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Witnesses: N45°E 11.53' POWER POLE
S80°W 66.68' POWER POLE
WEST 17.82' C-1- NE CORNER SECTION 6
WEST 32.68' REBAR WITH CAP
WEST 38.19' TELEPHONE RISER



Signed by Alan K. Bartlett Date 11/02/2000

Surveyor's Michigan License No. 35988

SURVEY &
REMONUMENTATION

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

JAN 31 2001

LIBER 4 PAGE 243

SECTION