

**SURVEY &  
REMONUMENTATION**

APR 26 1995

REMONUMENTATION  
**COMMISSION**  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

Nov 23 3 06 PM '94

*Bernice T. Stacey*  
REGISTER OF DEEDS  
BERRIEN COUNTY MICHIGAN

RATIFIED BY THE BERRIEN COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER MICHIGAN  
PUBLIC ACT 345 OF 1990

*[Signature]*  
10-27-94

For corners in  
BERRIEN  
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>4S</u> R <u>17W</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, V.J. Strebs, in a field survey on November 17, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1827 - William Brookfield, D.S. (set post)  
W. Oak 12 - N81 3/4°E - 29 Links  
W. Oak 13 - N74°W - 44 Links

11/23/94 111#7594 A66  
CORNER \$7.00  
11/23/94 111#7594 A66  
STATE REMON FEE \$2.00

1890 - Luther Hemingway  
Post & Stones

1917 - Dewey set iron - 52'W of N.E. Cor. Sec. 5-15-17 (stone)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Set 4" Dia. Concrete monument at government distance (82 links)  
54.12' West of N.E. corner Sec. 5-5-17 & on Township line

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

4" Dia concrete monument W/B.C.R.P. Brass cap  
Nail & Witness tag in 10" Oak - West - 110.92'  
Nail & Witness tag in 12" Triple Elm - S60°E - 145.90'  
1 1/2" Iron Pipe - S45°E - 29.45'  
Concrete monument W/B.C.R.P. Brass cap East - 54.12'

Signed by *[Signature]*  
Surveyor's Michigan License No. 26469



Date 21 NOVEMBER 1994

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983