

RATIFIED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

[Signature]
6-22-99

BERRIEN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

99 AUG 16 AM 9:29

BERNICE TRETHERWAY
REGISTER OF DEEDS
BERRIEN COUNTY, MICHIGAN

For corners in

Berrien	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 4S	R 17W J-10
	T	R
	T	R
	T	R
2. Property Controlling in Section	S	T R
	S	T R
3. Miscellaneous Property in Sec.	S	T R
	S	T R
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

08/16/99 111#9898 A99
CORNER \$7.00
08/16/99 111#9898 A99
STATE REMON FEE \$2.00

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, V.J. Strebs, in a field survey on 17 June, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CORNER NOT SET IN ORIGINAL SURVEYS

- 1972 & 1973 E.R. STEFAN
FOUND RAILROAD SPIKE
FACE OF PP S 12° E - 25.9'
EAST END OF TUBE N 20° E 50.6'
EDGE OF SIGN POST N 28° W 54.85'
- 1973 WIGHTMAN & ASSOCIATES, INC.
(FOUND RAILROAD SPIKE)
NAIL IN PP S 20° E 26.35'
NAIL IN GUARD POST N 45° E 43.88'
NAIL IN GUARD POST N 45° W 53.19'
- DATE UNKNOWN BERRIEN COUNTY ROAD COMMISSION (MONUMENT BOX)
PP S 20° E 26.35'
GUARD POST N 45° E 43.88'
GUARD POST N 45° W 53.19'

DEC 28 1999

SECTION



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" ROD IN MONUMENT BOX
CORNER WAS FOUND TO BE 0.35' SOUTH AND 1.73 EAST OF THE INTERSECTION OF QUARTER LINES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1" X 3' IRON PIPE WITH B.C.R.P. BRASS CAP IN MONUMENT BOX.

- WIT TAG IN P.P. S 10° E 26.31'
- WIT TAG IN CORNER FENCE POST N 15° W 73.10'
- WIT TAG IN 10" MAPLE S 45° W 53.46'
- EAST END 12" CMP N 40° E 50.60'

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS.
THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

Signed by *[Signature]*
Surveyor's Michigan License No. 26469

Date 5 AUG. 1999