

RAN BY THE BERRIEN COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER MICHIGAN  
PUBLIC ACT 345 OF 1990

**BERRIEN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BERRIEN  
(County)

Located In: \_\_\_\_\_ Corner Code # L - 13

- |                                       |   |           |   |            |               |
|---------------------------------------|---|-----------|---|------------|---------------|
| 1. Public Land Survey                 | T | <u>4S</u> | R | <u>17W</u> | <u>L - 13</u> |
|                                       | T | _____     | R | _____      | _____         |
|                                       | T | _____     | R | _____      | _____         |
|                                       | T | _____     | R | _____      | _____         |
| 2. Property Controlling<br>in Section | S | _____     | T | _____      | _____         |
|                                       | S | _____     | T | _____      | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S | _____     | T | _____      | _____         |
|                                       | S | _____     | T | _____      | _____         |
| 4. Lot No. _____, Recorded Plat _____ |   |           |   |            |               |
| Private Claims _____                  |   |           |   |            |               |

10/20/00 111#4516 A66  
CORNER \$7.00  
10/20/00 111#4516 A66  
STATE REMON FEE \$2.00

Register of Deeds Stamp & File  
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, V.J. Strebs, in  
a field survey on SEPT 23  
2000 do hereby state that under  
requirements of P.A. 74, Michigan P.A. of 1970,  
the corner points mentioned in lines 1 and 2  
above were in conformance with regulations  
and rules therefore as required in the current  
manual of survey instructions of the United  
States Department of the Interior, Bureau of  
Land Management or by a decree of a Court of  
Law and /or that the corner points mentioned  
in lines 3, 4 and 5 above were in conformance  
with the rules of the Michigan Board of Land  
Surveyors or by a Decree of a Court of Law;  
established, re-established, monumented,  
recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 WILLIAM BROOKFIELD, D.S.  
SET 1/2 MILE POST  
20" BEECH N 703/4° E 41 LINKS  
14" BEECH N 723/4° W 53 LINKS
- 1984 WIGHTMAN & ASSOC.  
FOUND 3/4" ROD IN MON. BOX  
PK IN PP N 50° W 79.45'  
PK IN FENCE POST N 45° E 48.10'  
FACE OF 18" MAPLE SOUTH 46.70' SOUTH 46.70'
- 1999 WIGHTMAN & ASSOC.  
FOUND 3/4" IRON IN MON. BOX  
N 1/4 CORNER SEC. 1 - T5S - R17W EAST 9.87'  
PK IN 17" MAPLE N 5° E 47.33'  
PK IN 17" MAPLE N 25° W 53.97'  
C/L OF PP S 55° W 63.92'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" ROD IN MON. BOX

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

RESET 1/2" ROD WITH 1" X 3' IRON PIPE W/ B.C.R.P. BRASS CAP, STAMPED 26469, 2000  
WITNESS TAG IN 16" MAPLE N 10° E 46.85'  
WITNESS TAG IN 18" MAPLE N 25° W 54.09'  
1/2" REBAR S 40° W 39.96'  
CENTER OF STREET SIGN POST S 50° E 43.69'  
N 1/4 CORNER SEC. 1 - T5S - R17W EAST 9.87'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

RECORDED  
 00 OCT 20 PM 3:34  
 REGISTER OF DEEDS  
 BERRIEN COUNTY, MICHIGAN



Signed by [Signature]  
Surveyor's Michigan License No. 26469

Date 19 OCT 2000

REMONUMENTATION