

RAISED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

*[Signature]*

**BERRIEN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE**

For corners in

BERRIEN (County) Located In: \_\_\_\_\_ Corner Code # M - 7

1. Public Land Survey T 4 S R 17 W M - 7  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_ 5.  
 Private Claims \_\_\_\_\_

10/20/00 111#4516 A66  
 CORNER \$9.00  
 10/20/00 111#4516 A66  
 STATE REMON FEE \$2.00

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, V.J. Strebs, in a field survey on SEPT. 21, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1827 WILLIAM BROOKFIELD, D.S.  
 SET POST TO SECTIONS 13 & 24  
 30" POPLAR S 7 2/3° W 21 LINKS  
 10" LYNN N 81/2° W 58 LINKS  
 SUPPLEMENT: CORNER TO SECS. 18 & 19 - T4S - R16W  
 NORTH 49 LINKS (32.34')

1898 C.B. PRATT COUNTY SURVEYOR  
 IRON UNDER STONE WITH CROCKERY AROUND  
 (NO WITNESSES)

1920 - 1973 BERRIEN COUNTY SURVEYOR'S NOTES  
 IRON - FENCE POST WEST 20.5'  
 36" ELM N 20° W 37.1'  
 18" WALNUT N.E. 27.1'  
 STONE NORTH 34.1'  
 GUY POLE N 88° W 28.9'

1946 - 1965 BERRIEN COUNTY ROAD COMMISSION  
 IRON  
 IRON WEST 33.0'  
 BOLT SPIKE IN 32" BEECH N 55° E 88.1'  
 15" BEECH WEST 38.3'  
 PP S.E. 34.9'

1972 ALTON HOWARD  
 (MONUMENT BOX)  
 NAIL IN POLE S 40° E 54.80'  
 NAIL IN POLE N 40° E 102.0'  
 NAIL IN POLE WEST 32.80' (CONTINUED ON BACK OF SHEET)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND MICHIGAN BRASS CAP IN MONUMENT BOX

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

RESET BRASS CAP WITH 1" X 3" IRON PIPE W/ B.C.R.P. BRASS CAP, STAMPED 26469, 2000  
 WITNESS TAG IN PP WEST 57.57'  
 WITNESS TAG IN PP S 30° E 69.62'  
 WITNESS TAG IN CORNER FENCE POST N 35° E 54.50'  
 S.W. CORNER SEC. 18 - 4 - 16 NORTH 32.39'  
 AND IS ASCERTAINED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *[Signature]*  
 Surveyor's Michigan License No. 26469

Date 19 OCT 2000

**SURVEY & REMONUMENTATION**

**JAN 31 2001**

**SECTION**

00 OCT 20 PM 3:34  
 REC'D  
 BARRIE TREATHEWAY  
 REGISTER OF DEEDS  
 BERRIEN COUNTY, MICHIGAN



1973 WIGHTMAN & ASSOCIATES  
(MON. BOX - CAP)  
TELEPHONE POLE N 80° W 32.89'  
PP S 30° E 54.72'  
IRON PIPE WEST 33.00'

1994 JOHN HUNT  
FOUND STANDARD MARKER IN MON. BOX  
1/2" REBAR @ CORNER FOR SECS. 18 & 19 - T4S - R16W  
NORTH 32.43'  
NAIL & TAG IN PP S 35° E 54.47'  
NAIL & TAG IN 6" WILD CHERRY N 30° W 59.03'  
C/L TELEPHONE CABLE BOX N 85° W 32.50'  
NAIL & TAG IN 8" APPLE S 50° E 86.52'

2  
9

**SURVEY &  
REMONUMENTATION**

**JAN 31 2001**

**SECTION**