

RATIFIED BY THE BERRIEN COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER MICHIGAN  
PUBLIC ACT 345 OF 1990

**BERRIEN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**

RECORDED

AUG 16 AM 9:29

GRACE TRETHERWAY  
REGISTER OF DEEDS  
BERRIEN COUNTY, MICHIGAN

For corners in

Berrien (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

- |                                       |         |             |              |              |
|---------------------------------------|---------|-------------|--------------|--------------|
| 1. Public Land Survey                 |         | T <u>4S</u> | R <u>17W</u> | M- <u>10</u> |
|                                       |         | T _____     | R _____      | _____        |
|                                       |         | T _____     | R _____      | _____        |
|                                       |         | T _____     | R _____      | _____        |
| 2. Property Controlling<br>in Section | S _____ | T _____     | R _____      | _____        |
|                                       | S _____ | T _____     | R _____      | _____        |
| 3. Miscellaneous<br>Property in Sec.  | S _____ | T _____     | R _____      | _____        |
|                                       | S _____ | T _____     | R _____      | _____        |
| 4. Lot No. _____, Recorded Plat _____ |         |             |              |              |
| 5. Private Claims _____               |         |             |              |              |

08/16/99 111#9898 A99  
CORNER \$7.00  
08/16/99 111#9898 A99  
STATE REMON FEE \$2.00

Register of Deeds Stamp & File Number

I, V.J. Strebs, in a field survey on 17 June, 1999  
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points  
mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as  
required in the current manual of survey instructions of the United States Department of the Interior,  
Bureau of Land Management or by a decree of a Court of Law and /or that the corner points  
mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of  
Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented,  
recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 WILLIAM BROOKFIELD, D.S.  
SET 1/2 MILE POST  
12" BEECH S 32 1/3° W 36 LINKS  
15" BEECH N 37 1/3° W 32 LINKS
- 1965 BERRIEN COUNTY ROAD COMMISSION  
ANGLE IRON  
12" ELM N 80° W 38.7'  
30" BEECH S 60° W 69.6'  
FENCE EAST IS 19' NORTH  
36" OAK S 30° W 63.4'  
3" PEAR N 88° E 36.9'  
3" PEAR S 45° E 55.9'
- 1975 WIGHTMAN & ASSOCIATES, INC.  
(FOUND ANGLE IRON)  
10" MAPLE N 15° E 41.40'  
IRON PIPE WEST 33.00'  
8" HICKORY N 30° W 48.71'

DEC 23 1999

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND ANGLE IRON.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1" X 3' IRON PIPE WITH B.C.R.P. BRASS CAP IN MONUMENT BOX.  
WEST 1/4 CORNER SECTION 30 - T4S - R16W NORTH 19.17'  
WIT TAG IN 24" BEECH S 60° W 48.39'  
WIT TAG IN 12" MAPLE N 35° E 42.18'  
IRON PIPE WEST 33.05'

Signed by [Signature]  
Surveyor's Michigan License No. 26469

Date 5 Aug. 1999

