

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY... 8 ... T. 4 ... S., R. 18 ... W.		C-5
2. PROPERTY CONTROLLING IN SECTION	T. ... N. S., R. ... E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. ... N. S., R. ... E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Projected line from N.E. cor. sec. 17 through N 1/4 cor. and doubled the distance. Projected line from S.W. cor. sec. 17 through W 1/4 cor. and doubled distance. Dug and found broken crockery and tile in old fence line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" x 48" pipe with plastic cap. Put broken crockery and tile around pipe, set steel and wood fence post beside pipe.
 S 88° E, 263.95', 32" Cottonwood, spike & tag
 S 64° E, 111.20', 4" & 5" Twin Cherry, spike & tag
 S 37° E, 105.79', 12" Cherry, spike & tag
 S 10° W, 99.04', 15" Ash, spike & tag
 On north side old drive 70' ± N.W. into marsh

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell DATE 5-21-79
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655