

ED BY THE BERRIEN COUNTY  
VEY PEER GROUP AS THE  
L CORNER UNDER MICHIGAN  
BLIC ACT 345 OF 1990

*\* Correct Town & Range RECORDED  
is T45, R18W -- rerecorded in L4, Pg. 256*

**Berrien County Remonumentation Program  
LAND CORNER RECORDATION CERTIFICATE**

NOV -8 PM 12:51

22-00 Filing Requirement of Act 74, Mich. P.A. 1970

BERRIEN TRETHERWAY  
REGISTER OF DEEDS  
BERRIEN COUNTY, MICHIGAN

corners in

Berrien (County)	Located In:	Corner Code #
Public Land Survey	T <u>5S</u> R <u>17W</u>	L-13
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
Property Controlling Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
Miscellaneous	S ___ T ___ R ___	___
Property in Sec.	S ___ T ___ R ___	___

11/08/00 111#6048 A66  
CORNER \$7.00  
11/08/00 111#6048 A66  
STATE REMON FEE \$2.00

Register of Deeds Stamp & File Number

Plat No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

I, Alan K. Bartlett, in a field survey on March 29, 2000 hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the provisions and rules therefore as required in the current manual of surveying of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed above.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

- JOHN MULLETT DS; WEST ON SOUTH SIDE OF SECTION 35 40.00 CHAINS SET POST 1/4 SECTION CORNER. WITNESSES: N40°E 32 LINKS 7" SUGAR, N40°W 35 LINKS 18" BEECH
- OWN BERRIEN COUNTY ROAD COMMISSION; BRICK & STONE. WITNESSES: SE 92' CORNER OF BARN, SW 69.7' 5" PEAR, NW 49.2' 14" APPLE, ADDED WITNESSES: N02°E 20' FENCE POST, EAST 13.7' N 1/4 POST SEC 1-T5S-R18W, S15°W 8' 13" APPLE, N05°W 17.3' T.P., N40°W 83' 30' MAPLE
- 1960 BOOK, V C PAGE 37; IRONS AND STONES, 2634.0' EAST OF THE SOUTHWEST CORNER OF SECTION, APPROX. 14.5' WEST OF CENTERLINE OF ROAD TO THE SOUTH. WITNESSES: NORTH 33.0' IRON PIPE, SE 17.5' TELEPHONE POLE, SW 11.5' STEEL ROAD SIGN POST.
- D. ZWAR- ABONMARCHE; 5/8" IRON ROD. WITNESSES: EAST 13.73' N 1/4 SEC 1-T5S-R18W
- D. ZWAR- ABONMARCHE; 5/8" IRON ROD. WITNESSES: EAST 13.73' N 1/4 SEC 1-T5S-R18W

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

AND "T" BAR WITH ROCKS AROUND, APPROX 10' NORTH OF CENTERLINE OF TOWNLINE ROAD AT WOOD FENCE CORNER (NORTH AND WEST CORNER APPROVED BY THE BERRIEN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

CONCRETE MONUMENT WITH BRASS CAP (MARKED 2000 & 35988). POSITION IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Witnesses:  
NORTH 50.07' 9" WALNUT  
EAST 52.53' 9" MAPLE  
N10°W 25.40' POST WITH PK NAIL  
N40°W 84.72' 36" MAPLE

By Alan K. Bartlett

Date 11/02/2000

Surveyor's Michigan License No. 35988



**SURVEY & REMONUMENTATION**

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1963  
REVISED OCT., 1995

JAN 31 2001

SECTION

LIBER 4

PAGE 239